



Reflected Ceiling Plan - Female Changing Room
1 : 50

North Point:

Scale Bar:

Revision Schedule				
Rev. No.	Date	Issuer	Checker	Revision Description
P01	28.11.25	KW	ZW	Issue to QS

- Proposed New Works:**
- Ceiling Tile System:**
- Option 1: British Gypsum Gyrex Bio 600x600
 - Option 2: Rockfon Koral 600x600
- Ceiling Plasterboard:**
- British Gypsum Gyproc Moisture Resistance 12.5mm
- Refer to manufacturer's specification for complete system (inc. fixtures and fixings)*
- Ceilings:**
- New ceiling grids
 - All new ceiling tiles to be set at 2400mm from floor finish level to underside of ceiling tile.
 - MEP specialist to confirm with Client if ceiling void are suitable new/amended services.
 - Trims, edges and joints to be assembled following manufacturer's recommendation.
 - Plasterboard ceiling as indicated.
- Bespoke Joinery:**
- All bespoke joinery (Five-At-Heart), lockers and towel stations to span from floor finish to topside of ceiling grid.
 - Ceiling tiles to sit flush to bespoke joinery.
- Wall Tiles (Floor to Ceiling Only):**
- Floor to ceiling tiles to be set from floor finish level up to the underside of ceiling grid system.
 - Appropriate waterproofing to edge trim to tiles applied, following manufacturer's recommendation.
- MEP (Ceiling penetrations):**
- Delabie Sporting 2 showers, left side - top side inletsfrom ceiling.
 - Delabie Sporting 2 showers, right side - back side inletsfrom wall partition
- Note:** Client to appoint MEP specialist to calculate drain flow rate to determine optimal drainage solutions to wet areas and changing space. Ventilation calculations to be undertaken by MEP to ensure Part F2 compliance.

A3
original sheet size