

Ceiling penetrations to be coordinated between MEP design team and Contractor MEP team. Note all penetrations to ceiling to be fitted with certified fire-stopping solution. E.G. Quellfire

1no. 18mm Plywood board and 2no. 15mm Fire Board layers to underside joist

Extent of flat timber section (refer to drawing 220001)

8no. 175x47 treated timber ceiling joists @ 400 centres. Appropriate fixings and intumescent sealant to manufacturer's performance specification, or to equivalent performance specification Contractor's supplier-manufacturer choice.


Noggins to the ends of ceiling joists

Approx. Joist Length 3003

Note: Refer to MEP drawings for location of proposed MEP equipment.

G49

G49



North Point: 

Scale Bar: 1:20 

Revision Schedule				
Rev. No.	Date	Issuer	Checker	Revision Description
P01	18/02/26	KW	ZW	Issued for Tender
P02	20/02/26	KW	ZW	Issued for Tender - Project Titling Amendment

Client 	Project Sport Wales - Switchgear Upgrade	Drawing Title PROPOSED RCP - GROUND FLOOR	
Status FOR TENDER	Drawn By Checked By Date KW ZW 02/27/17	Scale 1:20	Job Number Drawing Code Drawing Number Status Rev. 106023 HLN-XX-00-DR-A- 210003 S1 P02
© 2026 HLN Limited. All Rights Reserved. Check printed scale, responsibility is not accepted for errors scaling from this drawing, reproduction of digital media or measuring from this document. All construction information should be taken from figured dimensions only. Report doubts/ discrepancies to project Architect.		HLN Limited 21 Neptune Court, Vanguard Way, Cardiff. CF24 5PJ t: 0845 375 3298 e: info@hln.co.uk w: www.hln.co.uk	RIBA # Chartered Practice INVESTORS IN PEOPLE 

A3 original sheet size