
Kerb Bedding

Edging Kerb Bedding


EDGING KERB: 50mm x 150mm precast concrete bullnosed EBN Edging kerb.



15N/mm² concrete foundation and backing

Dropped Kerb Bedding


KERB: 125mm x 150mm BN Bullnosed pre-cast concrete kerb



Gen 3 concrete foundation and backing

Kerb Bedding

KERB: 125mm x 255mm Half-battered road kerb with a 125mm upstand. All kerbs and edging to be hydraulically pressed and to BS EN 1340:2003



15N/mm² concrete foundation and backing

Rev.	Initial	Description	Date
A	LC	Tender Issue	09/10/26

Status

For discussion

For approval

For construction

barcud

Job Title

Llys Pedr

Lampeter
Ceredigion
SA48 7DD

Drawing Title

Proposed External Works
Kerb Bedding

Drawing Type

Tender Drawing

DO NOT SCALE
If in Doubt - Ask!

Use only figured dimensions.
All dimensions to be confirmed on site.
Report any discrepancies to Trevor Hopkins Associates Ltd.

© All rights, including copyright, in the content of this document are owned or controlled for these purposes by Trevor Hopkins Associates Ltd. Except where expressly stated otherwise, you are not permitted to copy, reproduce, adapt or change in any way the content of this document for any other purpose whatsoever without the prior written permission of Trevor Hopkins Associates Ltd.

Drawing Number	Revision	Sheet
D-1305	A	05

(01239) 621010
design@trevorhopkins.com

Trevor Hopkins Associates Ltd

Parc House, Parc Teifi, Cardigan, Ceredigion, SA43 1EW

D:\THA Dropbox\THA Files\Drawings\00 Barcud\1305 - Llys Pedr, Lampeter\Tender\T-1305A.pln

Original: A1