Specimen shrubs

Latin name	Common name	Specification	Density/m2	Total Number
Corylus avellana	Hazel	Containerised, 10L full pot, 90-100cm height, multi stemmed, 3-5 stems	As shown	5
Sorbus aucuparia	Mountain Ash	Containerised, 10L full pot, 90-100cm height, multi stemmed, 3-5 stems	As shown	1

Mix A - wooded shade

Latin name	Common name	Specification	Density/m2	Percentage	Total Number	17.5 Total Area (m2)
Asplenium scolopendrium	Hart's Tongue Fern	Containerised, 5L full pot	5	20%	18	
Asplenium trichomanoides	Maidenhair Spleenwort	Containerised, 1L full pot	9	10%	16	
Astrantia major	Greater Masterwort	Containerised, 3L full pot	7	10%	12	
Galium odoratum	Sweet Woodruff	Containerised, 3L full pot	7	10%	12	
Hedera helix 'Needlepoint'	Ivy 'Needlepoint'	Containerised, 3L full pot	7	10%	12	
Luzula sylvatica	Wood Rush	Containerised, 5L full pot	5	20%	18	
Polypodium vulgare	Common Polybody	Containerised, 3L full pot	7	20%	25	
				100%		
Bulb Layer						
Galanthus nivalis	Common Snowdrop	Grade 8/10	15	n/a	263	

Mix B - grass & heath

Latin name	Common name	Specification	Density/m2	Percentage	Total Number	19.4 Total Area (m2)
Calluna vulgaris 'Alba'	Heather 'Alba'	Containerised, 3L full pot	7	20%	27	
Calluna vulgaris 'Peter Sparkes'	Heather 'Peter Sparkes'	Containerised, 3L full pot	7	20%	27	
Deschampsia flexuosa ' Tatra Gold'	Wavy Hair Grass ' Tatra Gold'	Containerised, 3L full pot	5	10%	10	
Festuca gautieri	Spiky Fescue	Containerised, 1L full pot	9	40%	70	
Molinia caerulea 'Moorhexe'	Purple Moor Grass 'Moorhexe'	Containerised, 3L full pot	5	10%	10	
				100%		

Mix C - mountain ledges

Latin name	Common name	Specification	Density/m2	Percentage	Total Number	9.5 Total Area (m2)
Alchemilla alpina	**Alpine Lady's Mantle**	Containerised, p9, full pot	12	10%	11	
Armeria maritima 'Morning Star White'	**Thrift 'Morning Star White'**	Containerised, 1L full pot	9	10%	9	
Asplenium trichomanoides	Maidenhair Spleenwort	Containerised, 1L full pot	9	5%	4	
Dryas octopetala	**Mountain Avens**	Containerised, p9, full pot	12	10%	11	
Festuca gautieri	Spiky Fescue	Containerised, 1L full pot	9	25%	21	
Phlox subulata 'Alba'	Moss Phlox	Containerised, p9, full pot	12	10%	11	
Sedum rupestre	Jenny's Stonecrop	Containerised, p9, full pot	12	10%	11	
Sempervivum tectorum	Common Houseleek	Containerised, p9, full pot	12	10%	11	
Thymus polytrichus	Wild Thyme	Containerised, 1L full pot	9	10%	9	
				100%		

Notes

1. Do not scale from this drawing.
2. All dimensions are in millimetres unless otherwise stated.
3. All setting out, levels and dimensions to be agreed on site.
4. This drawing must be read in conjunction with the relevant specification clauses and detail drawings.
5. Order of construction and setting out to be agreed on site.

Date	Suit	Rev	Description	Drawn by	Approved
05-11-26	S1	P01	DRAFT RIBA 4 issue for info	FF	FF
06-11-26	S1	P02	RIBA 4 tender issue	FF	FF

MAKE SPACE

Contact

E: hello@makespace.land

Make Space Landscape Architecture Limited
201 Manchester Road,
Altrincham,
WA14 5NU

Client

Eryri National Park Authority

Project

Yr Hen Stablau - Betws y Coed

Drawing size	Drawing scale	Workstage
A3	n/a	RIBA 4

Drawing title

Softworks Schedule

Drawing number	Suitability	Rev
0134-MS-XX-XX-DR-L-0004	S1	P02